

# FG Solar Mount Installation Guide

**By: Advanced Technology Structures Ltd** 

**Table of contents** 

**System Components** 

**System Layout** 

**Roof Attachment** 

Rail and to L-Bracket Attachment


**Microinverter Mounting and Grounding** 

**Standard System Grounding** 

**Modules Installation** 

**Installation Photos** 

# **Standard System Components**



## **Installation Guide**

- Rail: Supports PV.
   Use at least 2 rows per module. Fiberglas extrusion Standard Yellow
- Z-Bracket:
   (Aluminum/Steel)
   Used to secure rails through roofing material to building structure. 48" o/c x 2 rails supports
- 3. Z-Bracket Bolt ¼" x 2-1/2"

  Trox bolt with stainless

  steel and rubber washer
- 4. Module Mid Clamp:
  Used to fasten PV panels to mounting rails. Aluminum clamp with stainless steel bolt and aluminum friction plate.

# **System Layout and Installation Guide**

## PLANING YOUR FG INSTALLATIONS

The installation can be lout out with rails parallel to the rafters or perpendicular to the rafters.

Center the installation area over the structural members as much as possible.

Leave enough room to safely move around the array during the installation. Some building codes and fire codes require minimum clearances around such installations. Please confirm with local building code requirements.


### NOTE:

For he total width/length of the modules

### Add:

1" for each space between the modules for mid-clamps


1" for end clamps on each side.




ROOF-MOUNT PLAN

NOTE: Modules should be positioned so that rails are flush with edge of module or extending no more than 1/2" beyond edge of module. The modules should not extend past (overhang) the ends of rails.


### RAILS MAY BE PLACED PARALLEL OR PERPENDICULAR TO RAFTERS





## LAYOUT WITH RAILS PERPENDICULAR TO RAFTERS (RECOMMENDED)




## **Roof Attachment and L-Brackets**









GROUND-MOUNT SECTION
1:10

Assemble components as above


Install on Screw Type ground anchors or concrete pile footings

Use 4 x 5/16 anchor bolts for ground attachment.





## **Standard System and Grounding**



#### GROUNDING LUG MOUNTING DETAILS:


Details are provided for both the WEEB and Ilsco products. The WEEBLug has a grounding symbol located on the lug assembly. The Ilsco lug has a green colored set screw for grounding indication purposes. Installation must be in accordance with NFPA NEC 70, however the electrical designer of record should refer to the latest revision of NEC for actual grounding conductor cable size.

Required if not using approved integrated grounding microinveters

GROUNDING LUG - BOLT SIZE & DRILL SIZE		
GROUND LUG	BOLT SIZE	DRILL SIZE
WEEBLug	1/4"	N/A - Place in Top SM Rail Slot
IISCO Lug	#10-32	7/32"

- · Torque value depends on conductor size.
- See product data sheet for torque value.







## WEEBLUG CONDUCTOR - UNIRAC P/N 008002S:

Apply Anti Seize and insert a bolt in the aluminum rail and through the clearance hole in the stainless steel flat washer. Place the stainless steel flat washer on the bolt, oriented so the dimples will contact the aluminum rail. Place the lug portion on the bolt and stainless steel flat washer. Install stainless steel flat washer, lock washer and nut. Tighten the nut until the dimples are completely embedded into the rail and lug. TORQUE VALUE 10 ft lbs. (See Note on PG. A)

See product data sheet for more details, Model No. WEEB-LUG-6.7






**ILSCO LAY-IN LUG CONDUCTOR - UNIRAC P/N 008009P:** Alternate Grounding Lug - Drill, deburr hole and bolt thru both rail walls per table.

TORQUE VALUE 5 ft lbs. (See Note on PG. A)


See ILSCO product data sheet for more details, Model No. GBL-4DBT.

NOTE: ISOLATE COPPER FROM ALUMINUM CONTACT TO PREVENT CORROSION


# Remaining Modules Installation Guide



INSTALL REMAINING MID-CLAMPS: Proceed with module installation. Engage each module with previously positioned Midclamp assemblies.




POSITION T-BOLT ALIGNMENT MARKS: Verify that the position indicator(s) & T-bolt shaft(s) are angled in the correct position. Tighten to final torque.




**FINISH MODULE INSTALLATION:** Proceed with module installation. Engage each module with the previously positioned clamp assembly:


# **Bonding Mid-clamp and Trim**



**INSTALL MIDCLAMPS:** Midclamp is supplied as an assembly with a T-bolt for module installation. Clamp assemblies may be positioned in rail near point of use prior to module placement.




**INSERT MIDCLAMP ASSEMBLY:** Insert 1/4" T-Bolt into top slot of rail




**MIDCLAMP:** Rotate midclamp assembly and slide until clamp is against module frame. Do not tighten nut until next module is in position. Ensure bolt is perpendicular to rail.



**PLACE ADJACENT MODULE AGAINST CLAMPS:**Modules must be tight against clamps with no gaps.
Tighten nut to required torque.



**POSITION INDICATOR - SERRATED T-BOLT:**Verify the T-bolt position indicator is perpendicular to the rail.



**Inverter Grounding** 

